



City of Plymouth 2022 Infrastructure Improvement Program

Byron Street Reconstruction

July 20, 2022 @ 7:00 pm

Resident/Business Information Packet

Public Information Sessions

Prepared by:



Who can you contact with questions?

By Phone:

City of Plymouth Department of Municipal Services 734.453.7737
Chris Porman, Adam Gerlach, and Dave Cirilli

City of Plymouth City Hall 734.453.1234
Paul Sincock, City Manager

Wade Trim (City Engineers - Office) 734.947.9700
Shawn Keough, Project Engineer (cell preferred) 313.363.1434

Wade Trim (City Engineers - On the job during construction)
Liam Coleman, Project Inspector (cell) 313.588-1362
Greg Stanley, Construction Department Director (cell) 313.363.0420

By Email:

City of Plymouth DMS office dms@plymouthmi.gov

Wade Trim (City Engineers - Office)
Shawn Keough, Project Manager skeough@wadetrim.com
Brian Frisk, Project Engineer bfrisk@wadetrim.com

Safety is Important - Please use caution when walking, jogging, biking or driving in the construction area.

Byron Street Reconstruction and Storm Sewer Upgrades

General Description of the Work on Byron Street:

This project involves the complete reconstruction of Byron from Main to Harvey. Along with the new roadway, new storm sewer will be installed across the roadway along with some additional storm sewer upgrades to collect sump pump discharges from the various apartment buildings.

Improvement Project Details:

Anticipated Start Date: August 1, 2022 or August 8, 2022

Anticipated Duration: Work is anticipated to take approximately 5 weeks.

Storm Sewer Improvements:

- New 12-inch concrete storm sewer from the street to the Byron Drain
- New outfall structures at the Byron Drain
- New 8-inch PVC to connect sump pumps to storm sewer system

Road Reconstruction:

- Complete road reconstruction - new curb and gutter, new aggregate base and new asphalt
- New concrete drive approaches up to right-of-way line and misc. sidewalk repairs.

Anticipated Sequence of Construction

- | | |
|---|--------|
| 1. Mobilization and Traffic Control set up | Week 1 |
| 2. Pavement Removal | Week 1 |
| 3. Storm Sewer Improvements | Week 2 |
| 4. Road Excavation and New Stone Base | Week 3 |
| 5. Concrete Curb and Gutter, Driveways & Sidewalk | Week 3 |
| 6. Asphalt Paving (initial layer) | Week 4 |
| 7. Restoration | Week 5 |
| 8. Final Paving | Week 5 |

Contractor schedules are often subject to change due to weather, field conditions, and material availability.

Garbage Collection will remain on its normal collection day. If your garbage does not get picked up for some reason, please call the City Department of Municipal Services and they will assist in getting it collected.

Access to residences will be maintained throughout construction. Vehicular access to drive approaches will be interrupted for approximately 7 to 10 days when the new curb and gutter is poured. Notice will be given in advance of interruption so that people can get their cars out of the driveway.

The City is attempting to coordinate additional parking areas near the project area.

Safety is Important - Please use caution when walking, jogging, biking or driving in the construction area.