



City of Plymouth

2022 Infrastructure Improvement Program

**Union Street Storm Sewer Improvements and Pavement
Reconstruction**

September 21, 2022 @ 7:00 pm
City Hall – 2nd floor Commission Chambers

Resident/Business Information Packet

Public Information Sessions

Prepared by:



Who can you contact with questions?

By Phone:

City of Plymouth Department of Municipal Services 734.453.7737
Chris Porman, Adam Gerlach, and Dave Cirilli

City of Plymouth City Hall 734.453.1234
Paul Sincock, City Manager

Wade Trim (City Engineers - Office) 734.947.9700
Shawn Keough, Project Engineer (cell preferred) 313.363.1434

Wade Trim (City Engineers - On the job during construction)
Liam Coleman, Project Inspector (cell) 313.588-1362
Greg Stanley, Construction Department Director (cell) 313.363.0420

By Email:

City of Plymouth DMS office dms@plymouthmi.gov

Wade Trim (City Engineers - Office)
Shawn Keough, Project Manager skeough@wadetrim.com
Brian Frisk, Project Engineer bfrisk@wadetrim.com

Safety is Important - Please use caution when walking, jogging, biking or driving in the construction area.

Union Street Reconstruction and Storm Sewer Upgrades

General Description of the Work on Byron Street:

This project involves the partial street reconstruction/resurfacing of Union from Penniman to Church. New storm sewer will be installed under the roadway to replace older, cracked and deteriorated storm pipe. Union Street will be reconstructed in the area above the new storm sewer and resurfaced in other areas to create a new driving surface from Penniman to Church. Union will be closed to through traffic during the construction.

Improvement Project Details:

Anticipated Start Date: Week of September 26, 2022

Anticipated Duration: Work is anticipated to take approximately 4 to 5 weeks.

Storm Sewer Improvements:

- New 12-inch concrete storm sewer from Penniman to Church
- New 30-inch outlet storm sewer in vicinity of Wilcox property

Road Reconstruction includes:

- Complete road reconstruction of the area above the new storm sewer – this is envisioned to be the southbound lane and parking lane.
- Resurfacing of the areas not impacted by the storm sewer work (i.e. northbound lanes)
- Minor concrete curb replacement and misc. sidewalk repairs.

Anticipated Sequence of Construction

- | | |
|---|------------|
| 1. Mobilization and Traffic Control set up | Week 1 |
| 2. Pavement Removal | Week 1 |
| 3. Storm Sewer Improvements | Week 1 & 2 |
| 4. Road Excavation and New Stone Base | Week 3 |
| 5. Concrete Curb and Gutter, Driveways & Sidewalk | Week 3 & 4 |
| 6. Asphalt Paving | Week 4 |
| 7. Restoration | Week 5 |

Contractor schedules are often subject to change due to weather, field conditions, and material availability.

Garbage Collection will remain on its normal collection day. If your garbage does not get picked up for some reason, please call the City Department of Municipal Services and they will assist in getting it collected.

Access to residences will be maintained throughout construction. Vehicular access to drive approaches will be interrupted when the contractor is working directly in front of each address. Notice will be given in advance of interruption so that people can get their cars out of the driveway.

Main Street and Hamilton will both serve as primary detour routes while Union is under construction.

Safety is Important - Please use caution when walking, jogging, biking or driving in the construction area.

